

Latest News from Portastor



Modular REB for Temple Mills Depot

Working for Balfour Beatty Rail Projects, the most recent of a series of projects for RLE, Portastor's contract required the design, manufacture, delivery, installation and commissioning of 4No Modular REB's for the CTRL Temple Mills Depot CTRL852 Depot Signalling and Protection Works.

These special REB, each 72m² plan area were manufactured in 2 modular sections, pre-installed with all internal plant and tested before delivery to site.

Due to the location of some of the buildings (between roads on the approach to the depot building) and the overhead catenary, a combination of road and Palfinger PKR750 road-rail delivery vehicles were used to undertake final delivery into the depot from the loading point.

Following installation of modules onto the basework Portastor engineers undertook final assembly works including module seals and cosmetic finishes.



Portastor
New Lane, Huntington
York, England
YO32 9PR

Tel: 01904 656869
Fax: 01904 625872
Email: action@portastor.com
www.portastor.com